

Content of Sort a Recordset by User Name.vbs (Site 1)

' Description: Demonstration script that returns a list of all the users in the fabrikam.com domain, and then sorts that list alphabetically by name.

On Error Resume Next

Const ADS_SCOPE_SUBTREE = 2

```
Set objConnection = CreateObject("ADODB.Connection")
Set objCommand = CreateObject("ADODB.Command")
objConnection.Provider = "ADsDSOObject"
objConnection.Open "Active Directory Provider"
Set objCommand.ActiveConnection = objConnection
```

```
objCommand.Properties("Page Size") = 1000
objCommand.Properties("Searchscope") = ADS_SCOPE_SUBTREE
objCommand.Properties("Sort on") = "Name"
```

```
objCommand.CommandText =
"SELECT Name FROM 'LDAP://dc=fabrikam,dc=com' WHERE " _
& "objectCategory=user"
Set objRecordSet = objCommand.Execute
objRecordSet.MoveFirst
```

```
Do Until objRecordSet.EOF
Wscript.Echo objRecordSet.Fields("Name").Value
objRecordSet.MoveNext
Loop
```